

BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer

Yelahanka Division

B.B.M.P. Bengaluru - 64

No EE/YNK-D/E-PMT/09/2018-19 Dated: 27-2-2019


APPROVED TENDER SCHEDULE -'B'

Item-71

Name of Work:-Construction of culverts in ward no 04, Yelahanka Division

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri BHUMIREDDY DAMODAR REDDY	
				Rate	Rate in Words
1	Earthwork in excavation for foundation of structure like culverts, retaining wall etc., as per drawing and technical specification, including setting out, construction of shoring and bracing, dressing of sides and bottom, back filling with approved material, disposal of balance earth as per specification, including cost of labour, HOM etc., complete. In all kinds of soil by manual means. (P.No.256, I.No.34.15.1 of PW,P&IWD S.R 2018-19)	Cum	121.50	162.18	Rupees One Hundred Sixty Two and Paise Eighteen Only
2	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1) SR 2018-19	Cum	121.50	74.43	Rupees Seventy Four and Paise Forty Three Only
3	KSRRB 4-1.2: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with 40mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days complete as per specifications, MORTH specifications No. 408, (P.No.13, I.No.4-1.2 of PW,P&IWD S.R 2018-19)	Cum	15.75	4679.79	Rupees Four Thousand Six Hundred Seventy Nine and Paise Seventy Nine Only
4	Providing and laying Plain /reinforced cement concrete for side drains wall and bottom thickness 15cm using M20 nominal mix concrete with OPC cement at 300kg with 20mm and down size granite metal coarse aggregate at 0.69 cum and fine aggregate at 0.43 cum machine mixed well compacted for walls at bottom including centring shuttering cost of materials HOM of machineries curing etc.completeexcluding cost of steel as per MORTH specification No.1500,1700,2200 Page No 265 lte mo 37.59.2 SR 2018-19	Cum	46.80	6009.67	Rupees Six Thousand Nine and Paise Sixty Seven Only

Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri BHUMIREDDY DAMODAR REDDY	
			Rate	Rate In Words
5 KSRRB - M2300-14: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebtrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications MORTH Specification No. 1600 & 2200 for TMT bars Fe 500. (P.No.239, I.No.29.29.2 of PW, P&IWTD S.R 2018-19)	Tonns	3.47	62893.40	Rupees Sixty Two Thousand Eight Hundred Ninety Three and Paise Forty Only
6 Providing precast slab of 250 mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc.	Sqm	7.20	4605.30	Rupees Four Thousand Six Hundred Five and Paise Thirty Only
7 Providing precast slab of 100 mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc.	Sqm	61.20	1986.45	Rupees One Thousand Nine Hundred Eighty Six and Paise Forty Five Only

B. Damodhar 
Signature of the Contractor


Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.